

DRILL HOLES

DRILL HOLES

DRILL HOLES

BORDER REV. DATE: June 1, 2004

PROJECT DESCRIPTION

I. GENERAL

This project involves the modification of an existing Traffic Control Signal with street lighting at the intersection of MD 235 (Three Notch Rd) and the Walmart Entrance in St. Mary's County. The existing pedestrian signal heads shall be replaced by Countdown pedestrian signal heads with audible pushbuttons. MD 235 (Three Notch Rd) is assumed to run a north-south direction.

II. INTERSECTION OPERATION

- The intersection shall continue to operate in a NEMA four-phase, fully-actuated mode, with the MD 235 (Three Notch Rd) approaches running concurrently. The Exclusive left turn phase for the northbound approach of MD 235 (Three Notch Rd) shall remain in operation. The pedestrian phase across Walmart Entrance on recall shall now be a Countdown pedestrian phase with audible pushbuttons. The pre-emption phase for both approaches of MD 235 (Three Notch Rd) shall remain in operation. The Walmart Entrance approach shall continue to operate in its own phase.
- The existing full-traffic-actuated, eight-phase controller with all necessary equipment housed in a NEMA size "6" base-mounted cabinet shall be maintained at this intersection.
- SHA signal shop shall install APS control unit into controller cabinet. The Contractor shall deliver the Control Unit and audible pushbuttons to the SHA Signal Shop for testing and programming. Contact Mr. Ed Rodenhizer (410) 787-7652.

III. SPECIAL NOTES

- The Contractor shall be responsible for terminating all signal cables, to the appropriate terminals and shall properly label each cable.
- All controller cabinet wiring will be performed by the S.H.A. Signal Shop. Contact Mr. Ed Rodenhizer at (410) 787-7652 seventy-two hours in advance of intended work.
- All underground and overhead utilities shown on these plans are schematic only and may not be complete. The Contractor shall be responsible for notifying Miss Utility prior to construction so that all utilities may be located in the field. If the Contractor perceives that a conflict between the utilities and the traffic signal will occur, the Contractor shall notify the Project Engineer immediately so that the conflict may be resolved.
- APS will function as follows:
FOR WALMART ENTRANCE
 - When pedestrian locates and presses pushbutton for an extended time, the pushbutton unit will be Wait to cross Walmart entrance.
 - When WALK phase begins, the message will be a rapid tick which will last for the duration of the WALK phase.

The contact persons for District #5 are as follows:

Ms. Kim Tran
Assistant District Engineer - Traffic
Phone: (410) 841-1003

Mr. Andre Futrell
Assistant District Engineer - Maintenance
Phone: (410) 841-1002

Mr. John Mays
Assistant District Engineer - Utility
Phone: (410) 841-1005

Mr. Richard L. Daff, Sr.
Chief, Traffic Operations Division
Phone: (410) 787-7630

Mr. Ed Rodenhizer
Signal Shop
410-787-7652

Mr. Sonny Bailey
Sign Shop
410-787-7670

EQUIPMENT LIST (CONT.)

B. EQUIPMENT TO BE FURNISHED AND INSTALLED BY THE CONTRACTOR

ITEM NO.	DESCRIPTION	QUANTITY
1001	Maintenance of traffic per assignment.	1 EA
2002	Test Pit Excavation	2 C.Y.
5003	Removal of existing permanent pavement line markings	15 L.F.
5005	12" white heat applied permanent preformed thermoplastic pavement marking.	50 L.F.
6002	Standard type A combination curb and gutter 12" gutter pan 8" depth.	65 L.F.
6004	4" concrete sidewalk.	560 S.F.
6005	Detectable warning surfaces	44 S.F.
8001	12" LED Signal Head Section	27 EA
8002	2 wire Central Control unit	1 EA
8007	Audible/tactile pedestrian pushbutton station & signs.	2 EA
8014	LED 16" countdown pedestrian signal heads.	2 EA
8022	Remove and dispose of existing material & equipment per assignment. (Paid under MD 235 @ Macarthur)	1 EA
8034	Schedule 80 rigid PVC conduit up tp 4" - trenched.	15 L.F.
8038	No. 6 AWG stranded bare copper ground wire.	20 L.F.
8046	Install overhead sign.	1.5 S.F.
8056	Electrical cable - 2 conductor (No. 14 AWG).	125 L.F.
8058	Electrical cable - 5 conductor (No. 14 AWG).	140 L.F.


C. EQUIPMENT TO BE REMOVED

All removed signal materials are to become property of the contractor.

PHASE CHART

	1	2	3	4	5	6	7	8	9	10	11
	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)	(R) (Y) (G)
PHASE 1 & 6	R	R	←G-	←G-	←G-	G	G	←R-	←R-	DW	DW
1 & 6 CHANGE	R	R	←Y-	←Y-	←Y-	G	G	←R-	←R-	DW	DW
PHASE 2 & 6	G	G	←R-	←R-	←R-	G	G	←R-	←R-	WK	WK
PED CLEAR / COUNTDOWN	G	G	←R-	←R-	←R-	G	G	←R-	←R-	FL/DW	FL/DW
2 & 6 CHANGE	Y	Y	←R-	←R-	←R-	Y	Y	←R-	←R-	DW	DW
PHASE 4	R	R	←R-	←R-	←R-	R	R	←G-	←G-	DW	DW
4 CHANGE	R	R	←R-	←R-	←R-	R	R	←Y-	←Y-	DW	DW
PRE EMPT 1	G	G	←R-	←R-	←R-	G	G	←R-	←R-	DW	DW
PRE EMPT 1 CHANGE	Y	Y	←R-	←R-	←R-	Y	Y	←R-	←R-	DW	DW
FLASHING OPERATION	FL/Y	FL/Y	FL/←R	FL/←R	FL/←R	FL/Y	FL/Y	FL/←R	FL/←R	DARK	DARK

WIRING DIAGRAM



WIRING KEY

- A } 5-CONDUCTOR ELECTRICAL CABLE (NO. 14 A.W.G.)
- B } 2-CONDUCTOR ELECTRICAL CABLE (NO. 14 A.W.G.)
- C } 2-CONDUCTOR ELECTRICAL CABLE (NO. 14 A.W.G.)
- D } 2-CONDUCTOR ELECTRICAL CABLE (NO. 14 A.W.G.)
- E - STRANDED BARE COPPER GROUND WIRE (NO. 6 A.W.G.)
- EL - LOOP WIRE (NO. 14 A.W.G.) EXISTING
- ES - EXISTING UNDERGROUND SERVICE TO BE MAINTAINED BY SMECO

TOD NO:AT913-15
SHA NO:SM361A51/C51
MD235@MACARTHUR BLVD/
WAL-MART ENTRANCE

SHA		STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION	
MD 235 (THREE NOTCH RD) AND WALMART ENTRANCE			
LEXINGTON, MARYLAND			
GENERAL INFORMATION SHEET			
SCALE <u>NONE</u>		DATE <u>6/05/07</u>	
DESIGNED BY <u>J. ALLEN</u>		COUNTY <u>ST. MARY'S</u>	
DRAWN BY <u>ROB CICCHINI</u>		LOGMILE <u>18023515.58</u>	
CHECKED BY <u></u>		TIMS NO. <u>1968</u>	
F.A.P. NO. <u></u>		TOD NO. <u></u>	
TS NO. 3842A	DRAWING NO. 2 OF 2	SHEET NO. OF	