

UNREASONABLE DELAY EXISTING ONTO US 1.

ITEM	DESCRIPTION	UNIT	QTY.
1001	MAINTENANCE OF TRAFFIC PER ASSIGNMENT	EA.	1
8021	FURNISH AND INSTALL SAW CUT FOR SIGNAL (LOOP DETECTOR)	L.F.	122.0
8022	FURNISH AND INSTALL 1" ELECTRICAL CONDUIT - GALVANIZED SLEEVE	L.F.	10.0
8024	FURNISH AND INSTALL 2" SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED	L.F.	135.0
8033	FURNISH AND INSTALL ELECTRICAL HANDHOLE	EA.	1
8040	FURNISH AND INSTALL LOOP WIRE ENCASED IN FLEXIBLE TUBING (NO.14 AWG)	L.F.	396.0
8041	FURNISH AND INSTALL ELECTRICAL CABLE - 2 CONDUCTOR (ALUMINUM SHIELDED)	L.F.	700.0

- SLEEVE FOR DETECTOR WIRE.
- INSTALL ELECTRICAL HANDHOLE .
- INSTALL 2" SCHEDULE 80 RIGID PVC - TRENCHED, FROM NO.1 HANDHOLE TO NO.2 HANDHOLE ONLY.
- INSTALL 2 CONDUCTOR (ALUMINUM SHIELDED) ELECTRICAL CABLE FROM HANDHOLE NO.1 - NO.6 AND INTO CONTROLLER CABINET.

