PROJECT DESCRIPTION

I. GENERAL

This project involves the installation of presense and advance detection making the existing traffic signal full actuated at the intersection of MD 272 and I-95 off ramp in Cecil County.

MD 272 is assumed to run in an north-south direction.

II. INTERSECTION OPERATION

1. The intersection shall operate as a four-phase, full-actuated-mode with a lagging Exclusive/ Permissive left turn for southbound MD 272 onto the 1-95 Ramp. MD 272 approaches shall operate together and the Ramp shall operate alone.

2. The existing eight-phase controller housed in a NEMA size "6" base-mounted cabinet shall be utilizies. Three NEMA load switches and two 4-channelrack mounted amplifiers with power supply and panel shall be installed into the existing cabinet.

III. SPECIAL NOTES:


1. The Contractor shall be responsible for terminating all signal cables to the appropriate terminals and shall properly lable each cable. The Contractor shall contact Mr.Ed Rodenhizer (410- 787-5200) Chief of the Signal Shop 72 hours in advance to the internal controller wiring to have a Signal Shop representive present.


A. EQUIPMENT TO BE SUPPLIED BY SHA AND INSTALLED BY THE CONTRACTOR.

NO.	QUANTITY	DESCRIPTION
9001	2 EA.	Detector amplifiers 4-channelrack mounted.
9002	1 EA.	Detector panel.
9003	1 EA.	Rack power supply.
9004	3 EA.	NEMA load switch.

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR.

ITEM <u>NO.</u>	QUANTITY	DESCRIPTION
1001	1 EA.	Maintenance of Traffic.
1002	1 EA.	Modilization.
8011	780 L.F.	3" Schedule 80 rigid PVC conduit- trenched.
8012	36 L.F.	4" x 4" Wood sign supports.
8013	33 S.F.	Ground mounted sign W3-3 "NEW" (48" x 48").
8015	10 L.F.	1" electrical conduit galvanized sleeve.
8018	30 L.F.	1" non-metallic conduit for detector sleeve.
8021	7 EA.	Electrical handhole.
8025	130 L.F.	2-Conductor No. 14 AWG aluminum shielded.
8026	1220 L.F.	Loop wire encased in flexible tubing (14 AWG).
8027	265 L.F.	Sawcut for signalloop detector.
8032-A	5 EA.	Probe set with 500' leadin.
8047-A	65 L.F.	4" Schedule 80 PVC conduit- bored.





EQUIPMENT LISTS

PHASE CHART

1	2	3	4	5	6	7	8
R	R	R	(R)	(R)	(R)	R	(R)
Y	\bigcirc	TY-YY	(R) (Y) (Y) (G) (G)	Y		Ŷ	Y
G	(G) ((G-)(G)	(G)(G)	G	G	G	G

PHASE 2 & 6	G	G	G	G	G	R	R	R	4
6 CHANGE	Y	Υ	G	G	G	R	R	R	
PHASE 2 & 5	R	R	G ← G —	G —	G	R	R	R	<i>></i> H
2 & 5 CHANGE	R	R	G ← Y —	G Y —	Y	R	R	R	——
PHASE 4	R	R	R	R	R	G	G	G	+ -
4 CHANGE	R	R	R	R	R	Y	Υ	Y	
FLASHING OPERATION	FL/Y	FL/Y	FL/Y	FL/Y	FL/Y	FL/R	FL/R	FL/R	A


Wiring Key

A
B
C
With 500' lead-in.

F } 2— Conductor No.14 AWG G } aluminum shielded.


ES — Existing electrical service to be maintained.

NOTE: All remaining cables to be maintained.



STREET TRAFFIC STUDIES, LTD. 400 Crain Hwy, N.W. Glen Burnie, MD 21061 Ph (410) 590-5500 Fax (410) 590-6637

Task43GI.DGN



MD 272 AND NORTHBOUND I-95 RAMP

DRAWN BY: MILESKY COUNTY: _ LOG MILE: 07027212.73 CHECK BY: __ 08/09/00 F.A.P. NO. AV 718459 N\A SCALE: ____

SHEET NO. 3721B T.I.M.S. NO. D 912