

PROJECT DESCRIPTION

I. GENERAL

THIS PROJECT INVOLVES A TRAFFIC SIGNAL MODIFICATION IN CONJUNCTION WITH GEOMETRIC IMPROVEMENTS ALONG CRESTWOOD BOULEVARD TO PROVIDE EASTBOUND DUAL LEFT TURN LANES. THE MODIFICATION INVOLVES THE INSTALLATION OF A NEW POLE AND MAST ARM TO PROVIDE TRAFFIC SIGNAL HEADS FOR THE NEW LANE CONFIGURATION. BALLENGER CREEK PIKE (MD 351) IS ASSUMED TO RUN IN A NORTH-SOUTH DIRECTION..

II. INTERSECTION OPERATION

THE INTERSECTION WILL OPERATE IN A NEMA FOUR-PHASE, FULL TRAFFIC ACTUATED MODE. BALLENGER CREEK PIKE WILL OPERATE WITH EXCLUSIVE/PERMISSIVE LEFT TURN PHASING. CRESTWOOD BOULEVARD WILL OPERATE AS SPLIT PHASED. THE WESTBOUND RIGHT TURNS FROM CRESTWOOD BOULEVARD WILL OPERATE AS OVERLAP WITH THE SOUTHBOUND LEFT TURNS.


III. CONTROLLER REQUIREMENTS

THE EXISTING CONTROLLER AND ALL ASSOCIATED HARDWARE WILL BE MAINTAINED.

IV. SPECIAL NOTES


1. MAINTENANCE OF TRAFFIC WILL BE HANDLED BY THE CONTRACTOR UTILIZING THE FOLLOWING STANDARD PLATES FOR TRAFFIC CONTROL: 104.00-13, 104.00-19, 104.00-21-104.00-24, 104.17-01, 104.17-02, 104.39-02, 104.41-02, 104.48-01, 104.48-02, 104.49-01, 104.49-02, 104.81-01, 104.81-02.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PULLING ALL CABLE TO THE CABINET
3. ALL UNDERGROUND AND OVERHEAD UTILITIES SHOWN ON THESE PLANS ARE SCHEMATIC ONLY AND MAY NOT BE COMPLETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING MISS UTILITY PRIOR TO CONSTRUCTION SO THAT ALL UTILITIES MAY BE LOCATED IN THE FIELD. IF THE CONTRACTOR PERCEIVES THAT A CONFLICT BETWEEN THE UTILITIES AND THE CONSTRUCTION OF THE PROJECT WILL OCCUR, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.

PHASE CHART NORMAL OPERATION



PHASE 1 + 5	←G/R	←G/R	R	←G/R	←G/R	R	R	R	R	R	R	R/G>		DW	DW	DW	
1 + 5 CHANGE	1 + 5 MAY CHANGE TO PHASE 1 + 6, PHASE 2 + 5 OR PHASE 2 + 6																
PHASE 1 + 6	←G/G	←G/G	G	R	R	R	R	R	R	R	R	R		DW	DW	DW	
1 + 6 CHANGE	←Y/G	←Y/G	G	R	R	R	R	R	R	R	R	R		DW	DW	DW	
PHASE 2 + 5	R	R	R	←G/G	←G/G	G	R	R	R	R	R	R		DW	DW	DW	
2 + 5 CHANGE	R	R	R	←Y/G	←Y/G	G	R	R	R	R	R	R		DW	DW	DW	
PHASE 2 + 6	G	G	G	G	G	G	R	R	R	R	R	R		DW	DW	DW	
2 + 6 CHANGE	Y	Y	Y	Y	Y	Y	R	R	R	R	R	R		DW	DW	DW	
2 + 6 ALT	G	G	G	G	G	G	R	R	R	R	R	R		W	DW	DW	
PED. CLEARANCE	G	G	G	G	G	G	R	R	R	R	R	R		FL/DW	DW	DW	
2+6 ALT CHANGE	Y	Y	Y	Y	Y	Y	R	R	R	R	R	R		DW	DW	DW	
PHASE 3	R	R	R	R	R	R	←G	←G	G	R	R	R		DW	DW	DW	
3 CHANGE	R	R	R	R	R	R	←Y	←Y	Y	R	R	R		DW	DW	DW	
PHASE 3 ALT.	R	R	R	R	R	R	←G	←G	G	R	R	R		DW	W	DW	
PED CLEAR	R	R	R	R	R	R	←G	←G	G	R	R	R		DW	FL/DW	DW	
3 ALT CHANGE	R	R	R	R	R	R	←Y	←Y	Y	R	R	R		DW	DW	DW	
PHASE 4	R	R	R	R	R	R	R	R	R	←G	←G	G		DW	DW	DW	
4 CHANGE	R	R	R	R	R	R	R	R	R	←Y	←Y	Y		DW	DW	DW	
PHASE 4 ALT.	R	R	R	R	R	R	R	R	R	←G	←G	G		DW	DW	WK	
PED CLEAR	R	R	R	R	R	R	R	R	R	←G	←G	G		DW	FL/DW	FL/DW	
4 ALT CHANGE	R	R	R	R	R	R	R	R	R	←Y	←Y	Y		DW	DW	DW	
FLASHING OPERATION	FL/Y	FL/Y	FL/Y	FL/Y	FL/Y	FL/Y	FL/R	FL/R	FL/R	FL/R	FL/R	FL/R		DARK	DARK	DARK	

WIRING DIAGRAM



WIRING DIAGRAM

- | | |
|-------|---|
| A,B,E | 7 CONDUCTOR ELECTRICAL CABLE (#14 AWG) |
| C,F,H | 5 CONDUCTOR ELECTRICAL CABLE (#14 AWG) |
| H | 250' VIDEO DETECTION LEAD IN |
| G,J | 2 CONDUCTOR ELECTRICAL CABLE (#14 AWG)
FOR PUSH BUTTON |
| GW | GROUND WIRE |
| ⊕ | GROUND ROD (EX) |

EQUIPMENT LIST "A"

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY SHA

QUANTITY	UNITS	SPECIFICATION SECTION	DESRPTION
	NONE		

EQUIPMENT LIST "B"

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR

QUANTITY	UNITS	SPECIFICATION SECTION	DESCRIPTION
1	LS	104	Maintenance of Traffic.
1	LS	108	Mobilization.
1	CY	205	Test pit excavation.
5	CY	801	Concrete for signal foundation.
20	SF	813	Furnish and Install sheet aluminum signs consisting of: 2 ea. R10-4(f) 9"x12" - POLE MOUNTED 2 ea. R3-5(L) 30"x36" - MAST ARM MOUNTED 1 ea. R10-11(b) 24"x24" - MAST ARM MOUNTED
20	LF	805	3 In. schedule 80 rigid PVC conduit (trenched).
1	EA	816	Video detection camera.
1	EA	810	Control cable, 250', video detection camera to controller.
1	EA	818	27' steel pole with 60' mast arm
1	EA	818	10' pedestal pole
9	EA	814	12 In. vehicular signal head section.
4	EA	814	8 In. vehicular signal head section.
4	EA	814	12 In. pedestrian signal head section.
75	LF	810	Electrical cable - 2 conductor (NO.14 AWG).
100	LF	810	Electrical cable - 5 conductor (NO.14 AWG).
700	LF	810	Electrical cable - 7 conductor (NO.14 AWG).
2	EA	817	Pedestrian push button assembly.

PROJECT CONTACTS

THE CONTACT PERSONS FOR THIS PROJECT ARE AS FOLLOWS:

MR. JOHN CONCANNON
ASSISTANT DISTRICT ENGINEER - TRAFFIC
PHONE: (301) 624-8140

MS. ANDREA ABEND
DISTRICT UTILITIES ENGINEER
PHONE: (301) 624-8116

MR. DAVID COYNE
ASSISTANT DISTRICT ENGINEER - MAINTENANCE
PHONE: (301) 624-8106

MR. RICHARD DAFF
SR. CHIEF TRAFFIC OPERATIONS DIVISION
PHONE: 410)787-7630

WELLS & ASSOCIATES, LLC

TRANSPORTATION, TRAFFIC, AND PARKING CONSULTANTS
1420 Spring Hill Rd., Suite 600
McLean, VA 22102

Phone: (703) 917-6620 Fax: (703) 917-0739

5 Wirt St., SW, Suite 300

Leesburg, VA 20175

Phone: (703) 443-1442 Fax: (703)



MARYLAND DOT - STATE HIGHWAY ADMINISTRATION
Office of Traffic & Safety

TRAFFIC ENGINEERING DESIGN DIVISION
TRAFFIC SIGNAL DESIGN PLAN
BALLENGER CREEK PKWY (MD 351)
AT CRESTWOOD BOULEVARD

DRAWN BY: WTB
CHECKED BY: CT
SCALE: NTS
DATE: 01/25/05

F.A.P. NO.	
S.H.A. NO.	BW996M82
COUNTY:	FREDERICK
LOG MILE:	10035100.

TS NO. 3488 B - GI
T.I.M.S. NO. E434

SHEET NO.

2 OF 2