




EXISTING SIGNS TO BE REMOVED




PROPOSED SIGNS




EXISTING SIGNALS TO BE REMOVED



PROPOSED LED SIGNALS




NEMA PHASING




NOTE: PHASES ASSOCIATED BY A DASHED LINE WILL OPERATE CONCURRENTLY. PHASES ASSOCIATED BY A SOLID LINE WILL NOT OPERATE CONCURRENTLY.

US 40 IS ASSUMED TO RUN IN AN EAST-WEST DIRECTION



CONSTRUCTION DETAILS (CONT.)


- W. INSTALL 4 IN. SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED.
- X. INSTALL 4 IN. SCHEDULE 80 RIGID PVC CONDUIT - BORED.
- Y. INSTALL 3 IN. SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED.
- Z. INSTALL 2 IN. SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED.
- AA. INSTALL NON-INVASIVE MICROLOOP PROBE WITH LEAD-IN CABLE.
- BB. REMOVE EXISTING GROUND MOUNTED SIGN AND SUPPORTS.
- CC. INSTALL GROUND MOUNTED SIGN ON 1-4"X4" WOOD SIGN SUPPORT. NOTE: SIGN POSTS INSTALLED IN BRICK OR CONCRETE SHALL HAVE SLEEVED FOUNDATIONS MEETING THE REQUIREMENTS OF STANDARDS MD 812.05-01 AND MD 812.05-02. SLEEVED FOUNDATIONS ARE INCIDENTAL TO THE WOOD SIGN SUPPORTS.
- DD. INSTALL BASE MOUNTED CABINET AND CONTROLLER WITH IP-BASED VIDEO DETECTION INTERFACE EQUIPMENT, 2-WIRE APS CENTRAL CONTROL UNIT AND UPS BATTERY BACKUP. NOTE: INSTALL 2-2 IN. AND 2-4 IN. CONDUIT BENDS IN BASE. CAP UNUSED BEND.
- EE. INSTALL GROUND MOUNTED SIGN ON 1-4"X6" WOOD SIGN SUPPORT (DRILLED).
- FF. INSTALL 5 IN. SKIP WHITE HEAT APPLIED THERMOPLASTIC PAVEMENT MARKING LINE (3 FT. LINE, 3 FT. GAP).
- GG. PAVEMENT MARKING SYMBOL TO BE REMOVED BY OTHERS.






CONSTRUCTION DETAILS

- A. INSTALL 27 FT. TWIN MAST ARM POLE WITH 70 FT. AND 50 FT. MAST ARMS, LED SIGNAL HEADS, IP-BASED VIDEO DETECTION CAMERAS, 20 FT. LIGHTING ARM WITH LED LUMINAIRE, AND SIGNS. NOTE: INSTALL 1-3 IN. CONDUIT BEND IN POLE BASE.
- B. INSTALL 27 FT. TWIN MAST ARM POLE WITH 70 FT. AND 50 FT. MAST ARMS, LED SIGNAL HEADS, IP-BASED VIDEO DETECTION CAMERAS, 15 FT. LIGHTING ARM WITH LED LUMINAIRE, AND SIGNS. NOTE: INSTALL 1-3 IN. CONDUIT BEND IN POLE BASE.
- C. INSTALL 10 FT. BREAKAWAY PEDESTAL POLE WITH LED COUNTDOWN PEDESTRIAN SIGNAL HEAD, APS PUSHBUTTON AND SIGN (ORIENT PARALLEL TO CROSSWALK). NOTE: INSTALL 1-2 IN. CONDUIT BEND IN POLE BASE. REFER TO STANDARD MD 801.01-01 FOR FOUNDATION DETAILS. TOP OF FOUNDATION SHALL BE INSTALLED FLUSH WITH FINAL SIDEWALK GRADE.
- D. REMOVE EXISTING PEDESTRIAN SIGNAL HEAD, PUSHBUTTON AND SIGN FROM PEDESTAL POLE. INSTALL LED COUNTDOWN PEDESTRIAN SIGNAL HEAD, APS PUSHBUTTON AND SIGN (ORIENT PARALLEL TO CROSSWALK) ON EXISTING PEDESTAL POLE. PLUG UNUSED HOLES.
- E. INSTALL 3 IN. SCHEDULE 80 RIGID PVC CONDUIT - BORED FOR CARRIER PIPE.
- F. REMOVE EXISTING BASE MOUNTED CABINET AND CONTROLLER. REMOVE EXISTING FOUNDATION 12 IN. BELOW GRADE AND BACKFILL TO GRADE. CAP AND ABANDON EXISTING CONDUITS.
- G. REMOVE EXISTING SIGNAL POLE, ASSOCIATED EQUIPMENT AND SIGN. REMOVE EXISTING FOUNDATION 12 IN. BELOW GRADE AND MAKE FLUSH WITH FINAL GRADE. UTILITY COMPANY TO DISCONNECT EXISTING ELECTRICAL SERVICE.
- H. INSTALL 3 IN. SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED. REFER TO INTERCONNECT PLAN FOR DETAILS.
- I. INSTALL 100 AMP EMBEDDED METERED SERVICE PEDESTAL. NOTE: INSTALL 1-4 IN. AND 3-2 IN. CONDUIT BENDS IN BASE.
- J. INSTALL ELECTRICAL HANDHOLE.
- K. REMOVE EXISTING SIGNAL POLE, ASSOCIATED EQUIPMENT AND SIGNS. REMOVE EXISTING FOUNDATION 12 IN. BELOW GRADE AND MAKE FLUSH WITH FINAL GRADE.
- L. INSTALL ELECTRICAL HANDHOLE WITH LONG DIMENSION PERPENDICULAR TO ROADWAY.
- M. REMOVE EXISTING HANDHOLE. CAP AND ABANDON EXISTING CONDUITS AND BACKFILL TO GRADE.
- N. DISCONNECT, PULLBACK AND REROUTE EXISTING INTERCONNECT COMMUNICATION CABLE.
- O. PROPOSED VIDEO DETECTION ZONE.
- P. ABANDON EXISTING LOOP DETECTOR.
- Q. USE EXISTING HANDHOLE.
- R. REMOVE EXISTING PAVEMENT MARKING.
- S. INSTALL 12 IN. WHITE PERMANENT PREFORMED HEAT APPLIED THERMOPLASTIC PAVEMENT MARKING LINE.
- T. INSTALL 24 IN. WHITE PERMANENT PREFORMED HEAT APPLIED THERMOPLASTIC PAVEMENT MARKING LINE.
- U. INSTALL WHITE PREFORMED HEAT APPLIED THERMOPLASTIC PAVEMENT MARKING SYMBOL.
- V. INSTALL 4 IN. SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED. STUB AT UTILITY POLE NO. 6.

GEOMETRIC LEGEND



UTILITY LEGEND



APPROVALS	REVISIONS
<p>TEAM LEADER</p> <p>ASST. DIV. CHIEF</p> <p>DIVISION CHIEF</p> <p>OFFICE DIRECTOR</p>	<p>SIGNAL RECONSTRUCTION, 03/2013</p> <p>INSTALL APS/OFS</p> <p>SHA NO. XX650185-TIMS NO. L536</p> <p>INSTALL CPSL 11-12-2004</p> <p>SHA NO. AT3585185</p> <p>JWA CTS WNB JAB BEK TH</p>

SHA STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION

OFFICE OF TRAFFIC & SAFETY
TRAFFIC ENGINEERING DESIGN DIVISION

**US 40 (W. PATRICK STREET)
AT MCCAIN DRIVE
FREDERICK, MARYLAND**

TRAFFIC SIGNAL PLAN	
SCALE 1"=20'	DATE _____ CONTRACT NO. FR3315171
DESIGNED BY _____	COUNTY FREDERICK
DRAWN BY S. BLOSS	LOGMILE 10004012.15
CHECKED BY N. LEARY	TIMS NO. _____
FAP NO. _____	TOD NO. _____
TS NO. 1347B	DRAWING SP-1 OF 2 SHEET NO. 1 OF 5

RK&K
Rummel, Klepper & Kahl, LLP
81 MOSHER STREET | BALTIMORE, MD 21217
PH: (410) 728-2200 FAX: (410) 728-2160

Engineers Construction Managers Planners Scientists
www.rkk.com