

CONSTRUCTION DETAILS


- OVERHEAD POWER SERVICE FEED TO BE DISCONNECTED BY BGE FORCES.
- REMOVE EXISTING SIGNAL HEADS, SPAN WIRE AND ALL ASSOCIATED WIRING.
- REMOVE EXISTING STRAIN POLE, STREET LIGHTING ARM AND FOUNDATION 3 FT. BELOW GRADE.
- REMOVE EXISTING STRAIN POLE AND FOUNDATION 3 FT. BELOW GRADE.
- REMOVE EXISTING STRAIN POLE, STREET LIGHTING ARM, UTILITY EQUIPMENT, ALL ASSOCIATED SIGNAL WIRING AND FOUNDATIONS 3 FT. BELOW GRADE.

EXISTING SIGNAL HEADS TO BE REMOVED

1-4 5-8
Y R
12" 12"

NEMA PHASING

FLASHING
OPERATION



PROJECT DESCRIPTION

THIS PROJECT INVOLVES THE REMOVAL OF THE EXISTING INTERSECTION CONTROL BEACON AT THE INTERSECTION OF MD 155 (LEVEL RD) AND MD 462 (PARADISE RD)/ PARADISE DRIVE IN HARFORD COUNTY. MD 155 IS ASSUMED TO RUN IN AN EAST-WEST DIRECTION. THE EXISTING I.C.B. WILL BE REPLACED WITH A SINGLE LANE ROUNDABOUT FOR TRAFFIC CONTROL.

TO I-95

MD 155 (LEVEL ROAD)

WEBSTER RD

MD 462
(PARADISE RD)

WEBSTER RD
(DRIVEWAY)

EQUIPMENT LIST "A"

A. EQUIPMENT TO BE SUPPLIED BY THE SHA.
NONE

EQUIPMENT LIST "B"

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR.

CATEGORY CODE	DESCRIPTION	UNIT	QUANTITY
800000	REMOVE AND DISPOSE OF EXISTING TRAFFIC SIGNAL EQUIPMENT	LS	1

EQUIPMENT LIST "C"

C. EQUIPMENT TO BE REMOVED BY THE CONTRACTOR AND RETURNED TO THE SHA.

THE EXISTING CABINET AND CONTROLLER TO BE REMOVED BY THE CONTRACTOR SHALL BE PICKED UP BY THE SHA. ALL OTHER MATERIALS AND EQUIPMENT REMOVED BY THE CONTRACTOR SHALL BECOME THE PROPERTY OF THE CONTRACTOR. THE CONTRACTOR SHALL CONTACT MR. ED RODENHIZER 72 HOURS PRIOR TO CONSTRUCTION.

GENERAL NOTES

- CONTRACTOR SHALL COORDINATE WITH BGE FOR POWER SERVICE FEED REMOVAL.

SHA

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION

OFFICE OF TRAFFIC & SAFETY
TRAFFIC ENGINEERING DESIGN DIVISION

MD 155 (LEVEL RD) AND
MD 462 (PARADISE ROAD)
WEBSTER, MARYLAND

TRAFFIC SIGNAL PLAN

SCALE 1"=20' DATE 4-12-1978 CONTRACT NO. H-764-451-485

DESIGNED BY JOHN BOLING COUNTY HARFORD

DRAWN BY JOHN BOLING LOGMILE 12015504.74

CHECKED BY WILLIAM RICHARDSON TMS NO. 1-715

FAP NO. TOD NO.

TS NO. 1603C DRAWING SG-1 OF 1 SHEET NO. 36 OF 50

APPROVALS	REVISIONS
TEAM LEADER	REMOVAL OF EXISTING SIGNAL DUE TO INSTALLATION OF ROUNDABOUT
ASST. DIV. CHIEF	BJG 2/17/2010
DIVISION CHIEF	B 1/24/2010
OFFICE DIRECTOR	SHA NO. XX4485185 TMS NO. J842 4/1/2010
	NML BM DJD
	A ASBUILT
	SHA NO. H764451485
	1/21/1981
	TMZ

RK&K

Rummel, Klepper & Kahl, LLP

81 MOSHER STREET | BALTIMORE, MD 21217

PH: (410) 728-2900 FAX: (410) 728-3100

Engineers Construction Managers Planners Scientists

www.rkk.com