



**GENERAL NOTES**

1. THE LOCATION OF PROPOSED GEOMETRICS MUST BE CONFIRMED PRIOR TO THE INSTALLATION OF SIGNAL EQUIPMENT.

2. ALL UNDERGROUND AND OVERHEAD UTILITIES SHOWN ON THESE PLANS ARE SCHEMATIC ONLY AND MAY NOT BE COMPLETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING MISS UTILITY PRIOR TO THE CONSTRUCTION SO THAT ALL UTILITIES MAY BE LOCATED IN THE FIELD. IF THE CONTRACTOR PERCEIVES THAT A CONFLICT BETWEEN UTILITIES AND THE TRAFFIC SIGNAL WILL OCCUR, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.

**CONSTRUCTION DETAILS**

A. REMOVE EXISTING SIGNAL HEAD AND INSTALL NEW SIGNAL HEAD IN SAME LOCATION - USE EXISTING WIRING

B. INSTALL OVERHEAD SIGN ON EXISTING MAST ARM AS SHOWN

C. REMOVE EXISTING HANDHOLE

D. INSTALL 3 IN. SCHEDULE 80 RIGID ELECTRICAL CONDUIT - TRENCHED (CONNECT TO EXISTING CONDUIT)

E. INSTALL ELECTRICAL HANDHOLE

F. REMOVE EXISTING OVERHEAD SIGN

GEOMETRIC LEGEND	
EXISTING	----
PROPOSED	=====
UTILITY LEGEND	
AERIAL CABLE	---
ELECTRICAL	---
TELEPHONE	---
GAS	---
SEWER	---
WATER	---
CABLE TV	---

**TRAFFIC CONCEPTS, INC.**

325 Gambrills Road  
Suite B  
Gambrills, MD 21054  
(410) 923-7101  
FAX: (410) 923-6473  
EMAIL: TRAFFIC@TRAFFIC-CONCEPTS.COM

APPROVALS		REVISIONS	
TEAM LEADER		1. GEOMETRIC IMPROVEMENTS / SIDE STREET SPLIT PHASING	
ASST. DIV. CHIEF		2. MODIFICATIONS DUE TO GEOMETRIC IMPROVEMENTS	
DIVISION		3. REPLACE WOODSDALE ROAD DETECTION / ADD EP LT FOR WOODSDALE RD	
OFFICE DIRECTOR		4. 4-12-06 - Tims # H272	

TRAFFIC SIGNALIZATION PLAN			
SCALE	1" = 20'	DATE	10-20-86
CONTRACT NO.	11-520-501502-470	DESIGNED BY	E. SIMMERS
COUNTY	HARFORD	DRAWN BY	E. SIMMERS
LOGMILE	12092400.19	CHECKED BY	S. SENZI
T.I.M.S. NO.	K-289	F.A.P. NO.	NA
TOD NO.		DRAWING NO.	TS-2241 E
SHEET NO.	1	OF	2

FILE PATH: M:\2400\2481\signal\md924@wooddale.dgn  
DATE: Wednesday, March 24, 2010 AT 10:01 AM