#### PROJECT DESCRIPTION

GENERAL

THIS PROJECT INVOLVES THE INSTALLATION OF A TEMPORARY TRAFFIC SIGNAL AT THE INTERSECTION OF CHERRY HILL ROAD AT PROSPERITY DRIVE IN MONTGOMERY COUNTY.

## INTERSECTION OPERATION

A SYSTEM CONTROLLER HOUSED IN A BASE MOUNTED CABINET SHALL BE INSTALLED AT THIS LOCATION. THE INTERSECTION WILL OPERATE IN A FULLY ACTUATED MODE USING 6 NEMA PHASES.

## SPECIAL NOTES

I. THE FOLLOWING CONTACT PEOPLE FOR THIS PROJECT ARE AS FOLLOW:.

MR. MIKE KINNEY, MCDPWT (FOR SURVEILLANCE CAMERA) PHONE: (240) 777-8760

MR. LEE STARKLOFF, ASSISTANT DISTRICT ENGINEER-TRAFFIC MR. DENNIS MCMAHAN, ASSISTANT DISTRICT ENGINEER-CONSTRUCTION PHONE: (301) 513-7336 MR. RALEIGH MEDLEY, ASSISTANT DISTRICT ENGINEER-MAINTENANCE PHONE: (301) 513-7300
MR. AUGIE REBISH, ASSISTANT DISTRICT ENGINEER-UTILITY PHONE: (301) 513-7300
MR. RICHARD L. DAFF, Sr., CHIEF TRAFFIC OPERATIONS DIVISION PHONE: (410) 787-7630 MR. BOBBY GONZALES, TRAFFIC ENGINEER MCDPWT PHONE: (240) 777-8761

2. MAINTENANCE OF TRAFFIC WILL BE HANDLED BY THE CONTRACTOR UTILIZING THE STANDARD PLATES FOR TRAFFIC CONTROL:

### **EQUIPMENT LIST**


A. EQUIPMENT TO BE SUPPLIED BY THE ADMINISTRATION.

CATEGORY CODE NO.	DESCRIPTION	UNITS	QUANTITY
900000	EIGHT PHASE FULLY ACTUATED SOLID STATE DIGITAL CONTROLLER WITH L.A.U, L.A.U PANEL AND HARNESSES HOUSED IN A NEMA SIZE '6' BASE MOUNTED CABINET	EA	1
973023	FLAT SHEET ALUMINUM SIGNS, (BLUE OR GREEN) R10-12 (36" × 42") D3-2 (VAR. X 16")	SF EA EA	40.8 1 3

B FOLIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR

B. EQUIPMENT	10 BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR.		
CATEGORY CODE NO.	DESCRIPTION	UNITS	QUANTITY
120500	MAINTENANCE OF TRAFFIC	LS	1
203030	TEST PIT EXCAVATION	CY	4
585624	24" HEAT APPL. WHT. PERM. PREF. THER. PVT. MARK.	LF	140
585620	12" HEAT APPL. WHT. PERM. PREF. THER. PVT. MARK.	LF	375
800000	2" SCHED. 80 PVC CONDUIT - TRENCHED	LF	50
800000	REMOVE AND DISPOSE EXISTING EQUIPMENT	LS	1
801004	CONCRETE FOR SIGNAL FOUNDATIONS	CY	16
801607	INSTALL SHEET ALUMINUM SIGN	SF	41
805135	4" SCHED. 80 PVC CONDUIT - TRENCHED	LF	18
805140	3" SCHED. 80 PVC CONDUIT - TRENCHED	LF	21
811003	HANDHOLE	EΑ	3
816001	VIDEO DETECTION CAMERA	EA	3
816010	PRE-MANUFACTURED CABLE TO CAMERA TO CONTROLLER (250' LENGTH CABLE)	EΑ	3
818009	14" x 32' STRAIN POLE (2 PLY)	EA	3
831010	250 WATT HPSV LUMINAIRE W/PHOTOCELL	EA	3
832020	NO. 6 AWG STRANDED BARE COPPER GROUND WIRE	LF	375
837001	GROUND ROD	EA	4
860263	12" PEDESTRIAN SIGNAL HEAD SECTION- POLE MOUNT	EA	4
860272	12" VEHICULAR SIGNAL HEAD SECTION	EΑ	33
866103	15' LIGHTING ARM FOR SIGNAL STRUCTURE	EΑ	3
861105	2-COND., NO. 14 AWG ELECT. CABLE	LF	510
861106	3—COND., NO. 14 AWG ELECT. CABLE	LF	340
861107	5-COND., NO. 14 AWG ELECT. CABLE	LF	900
861108	7-COND., NO. 14 AWG ELECT. CABLE	LF	980
861116	2 COND., NO. 12 AWG TRAY CABLE	LF	470
869102	STEEL SPAN WIRE 3/8 INCH DIAMETER	LF	480
871202	INSTALL CONTROLLER AND CABINET - BASE MT.	EA	1

C. MATERIALS TO BE REMOVED BY THE CONTRACTOR. ALL MATERIALS TO BE REMOVED BY THE CONTRACTOR SHALL BECOME PROPERTY OF THE CONTRACTOR.



# PHASE 3E

SHEET NO.

MARYLAND DOT - STATE HIGHWAY ADMINISTRATION
Office of Traffic & Safety Office of Traffic & Safety TRAFFIC ENGINEERING DESIGN DIVISION
GENERAL INFORMATION PLAN

CHERRY HILL ROAD AT PROSPERITY DRIVE



l BY₌	JAMES ALLEN Jr.	F.A.P. NO.		TS NO.
ED BY:		S.H.A. NO.	M08365I70	4116C
<b>a</b>	NTS	COUNTY:	MONTGOMERY	T.I.M.S. NO.
	APRIL, 2002	LOG MILE:		F142