FHWA	STATE	FED. AID	SHEET	TOTAL
REGION NO		PROJ. NO	NO.	SHEETS
3	MD.	SEE TITLE SHEET		

Intersection Operation

This intersection is to initially operate in a NEMA four phase, semi—traffic—actuated mode. There will be an exclusive/permissive left turn for the southbound movement of MD 355 and a right turn overlap for the westbound to northbound movement. The through movements for MD 355 will operate concurrently. The Watkins Mill Road movement will operate alone.

An eight phase, full—traffic—actuated, solid state digital controller with seven two—channel time delay output loop detector amplifiers housed in a base mounted cabinet are to be installed at this location.

Construction Details

- A. Install base mounted cabinet/controller with all necessary equipment (Note: two 4 in., 90—degree (Schedule 40) PVC bends, one 3 in., 90—degree (Schedule 40) PVC bend, and one 2 in., 90—degree (Schedule 80) PVC bend).
- B. Install 12 in. x 30 ft. steel strain pole with 15 ft. luminaire arm, 250 watt HPS luminaire, and all necessary equipment for an overhead type B—14 electrical service (Note: two 3 in., 90—degree (Schedule 40) PVC bends, and one 2 in., 90—degree (Schedule 80) PVC bend). [Use four 1—3/4 in. x 90 in. anchor bolts.]
- C. Install 12 in. x 30 ft. steel strain pole with 20 ft. luminaire arm, and 250 watt HPS luminaire (Note: one 2 in., 90—degree (Schedule 40) PVC bend). [Use four 1—3/4 in. x 90 in. anchor bolts.]
- D. Install handhole.

- E. Install 1 in. liquid tight, non-metallic conduit for loop detector sleeve.
- F. Install 2 in. polyvinyl chloride (Schedule 40) electrical conduit trenched.
- G. Install 2 in. polyvinyl chloride (Schedule 80) electrical conduit trenched.
- H. Install 3 in. polyvinyl chloride (Schedule 80) electrical conduit slotted.
- J. Install 3 in. polyvinyl chloride (Schedule 40) electrical conduit trenched.
- K. Install 4 in. polyvinyl chloride (Schedule 40) electrical conduit trenched.
- L. Install 4 in. polyvinyl chloride (Schedule 80) electrical conduit slotted.
- M. Install 6 ft. x 30 ft. quadrupole type vehicle loop detector (2-4-2 turns).
- N. Install 3/8 in. steel span wire and vehicle signal heads as shown.
- O. Install 3/8 in. steel span wire, 1/4 in. tether wire, vehicle signal head, and signs as shown.
- P. Install 3/8 in. steel span wire, 1/4 in. tether wire, vehicle signal heads (polycarbonate) and sign as shown (Note: Provide approximately 50 ft. of additional electrical cable for each signal head for use during roadway construction phasing).
- Q. Install 3/8 in. steel span wire and vehicle signal heads as shown (Note: Provide approximately 50 ft. of additional electrical cable for each signal head for use during roadway construction phasing).
- R. Remove existing electrical service.
- S. Use existing handhole. Pull back existing interconnect cable and re—run in new conduit to new controller.
- T. Remove existing handhole.
- U. Cap and abandon existing conduit.
- V. Remove existing steel pole and all attached equipment.

<u>Equipment List "A"</u>

Equipment to be supplied by the SHA.

Equipment to be supplied by the SHA.				
Quantity	Unit	Description		
1	EA	Eight phase, full—traffic—actuated, solid state digital controller with LAU panel (to be used in a NEMA four phase semi—traffic—actuated mode) housed in a base mounted cabinet.		
7	EA	Two—channel time delay output vehicle loop detector amplifier and harness.		
1	EA	8 in./12 in., one—way, five section (8 in. R,Y,G/12 in. YA,GA) adjustable traffic signal head — span wire mount.		
4	EA	12 in., one—way, three section (R,Y,G) adjustable traffic signal head— span wire mount.		
2	EA	12 in., one—way, three section (R,Y,G) polycarbonate adjustable traffic signal head — span wire mount.		
4	EA	12 in., one—way, five section (R,Y,YA,G,GA) polycarbonate adjustable traffic signal head — span wire mount.		
1	EA	12 in., one—way, five section (R,Y,YA,G,GA) adjustable traffic signal head — span wire mount.		
33	SF	Sheet aluminum signing. [To consist of one 36 in. x 42 in. R10—12 two 30 in. x 36 in. R3—5(L), and one 30 in. x 36 in. R3—5(R) signs for span wire mounting.]		

Equipment List "B"

Equipment to be furnished and/or installed by the Contractor.

Quantity	Unit	Description	
5	CY	Test pit excavation.	
4	EA	30 ft. steel strain pole.	
8	EA	Handhole.	
500	LF	Sawcut for signal loop detector.	
1325	LF	Loop detector wire (No. 14 A.W.G.) encased in flexible tubing.	
475	LF	2—conductor (aluminum shielded) electrical cable (No. 14 A.W.G.).	
750	LF	2-conductor electrical tray cable (No. 12 A.W.G.).	
200	LF	5-conductor electrical cable (No. 14 A.W.G.).	
1325	LF	7-conductor electrical cable (No. 14 A.W.G.).	
100	LF	Bare copper ground wire (No. 6 A.W.G.)	
90	LF	3-wire electrical cable (No. 4 A.W.G.) for electrical services.	
450	LF	1/4 in. tether wire.	
600	LF	3/8 in. steel span wire.	
50	LF	1 in. liquid tight, flexible, non-metallic conduit for loop detector sleeve.	
100	LF	2 in. polyvinyl chloride (Schedule 40) electrical conduit — trenched.	
20	LF	2 in. polyvinyl chloride (Schedule 80) electrical conduit — trenched.	
20	LF	3 in. polyvinyl chloride (Schedule 40) electrical conduit — trenched.	
150	LF	3 in. polyvinyl chloride (Schedule 80) electrical conduit — slotted.	
100	LF	4 in. polyvinyl chloride (Schedule 80) electrical conduit — slotted.	
140	LF	4 in. polyvinyl chloride (Schedule 40) electrical conduit — trenched.	
14	CY	Concrete foundation for signal equipment.	
8	EΑ	Ground rod $-3/4$ in. diameter x 10 ft. length.	
1	EA	15 ft. Luminaire arm with 250 watt HPS luminaire.	
3	EA	20 ft. Luminaire arm with 250 watt HPS luminaire.	
1	EA	Control and distribution equipment (120/240V, one phase, three wire system).	
9	EA	Install traffic signal head — span wire mount.	
33	SF	Install sheet aluminum signing — overhead mount.	
1	EA	Install base mounted cabinet.	
LS	LS	Removal of existing traffic signal equipment.	

Equipment List "C"

Equipment to be removed by the contractor and delivered to the MCDOT Systems Technical Center, 1283 Seven Locks Road, Building "C", Rockville, MD. 20852. A twenty—four (24) hour notice is required prior to delivery. Contact Mr. Emil Wolanin at (301) 217—2208.

Quantity Unit Description

Pole Mounted cabinet/controller.


Twin Mast Arm pole and Arms.

EA Mast Arm pole and Arm.


Traffic Signal Head.

EA Overhead Mounted Sign.

EA



Phase Chart



Maintenance of Traffic
Phase 1 Stage 2

