#### PROJECT DESCRIPTION

THIS PROJECT INVOLVES THE MODIFICATION OF AN EXISTING TRAFFIC CONTROL SIGNAL AT THE INTERSECTION OF MD 650 AND ELTON ROAD IN MONTGOMERY COUNTY. A NEW PEDESTRIAN SIGNAL IS BEING INSTALLED ACROSS THE NORTH LEG OF MD 650.

MD 650 IS ASSUMED TO RUN IN A NORTH-SOUTH DIRECTION.

#### INTERSECTION OPERATION

THE INTERSECTION CURRENTLY OPERATES AS A NEMA FIVE-PHASE, SEMI-TRAFFIC-ACTUATED MODE WITH A CLEARANCE PHASE FOR N.B. AND S.B. MD 650, A RIGHT TURN OVERLAP FOR N.B. MD 650, A CONCURRENT PEDESTRIAN PHASE ACROSS THE EAST LEG OF ELTON ROAD AND THE I-495 RAMP, AND AN ALTERNATE PEDESTRIAN PHASE ACROSS THE NORTH LEG OF MD 650.

### CONTROLLER REQUIREMENTS

THE EXISTING FULL-TRAFFIC-ACTUATED, EIGHT-PHASE CONTROLLER HOUSED IN A NEMA "6" BASE MOUNTED CABINET IS BEING USED.

WIRING DIAGRAM

## 

PHASING CHART

# EQUIPMENT LIST "A"

A. EQUIPMENT TO BE FURNISHED/OR INSTALLED BY MSHA.

ITEM NO. QUANTITY DESCRIPTION
NONE

CONTACT PERSONS FOR DISTRICT 3 ARE AS FOLLOWS:

MR, LEE STARKLOFF ASSISTANT DISTRICT ENGINEER - TRAFFIC (301) 513-7318 MR. WAYNE MOWDY
ASSISTANT DISTRICT ENGINEER - MAINTENANCE
(301) 513-7304

MR. AUGIE REBISH
ASSISTANT DISTRICT ENGINEER - UTILITIES
(301) 513-7350

CONTACTS FOR OFFICE OF TRAFFIC AND SAFETY

MR. RICHARD DAFF, SR. CHIEF, TRAFFIC OPERATIONS (410) 787-7630

MR. EUGENE BAILEY TEAM LEADER SIGN OPERATIONS (410) 787-7676

MR. ROBERT SNYDER
ASSISTANT DIVISION CHIEF,
TRAFFIC OPERATIONS
(410) 787-7631

MS. DARLENE EIDE SUPPLY OFFICE SIGNAL SHOP WAREHOUSE (410) 787-7668

MR. ED RODENHIZER
TEAM LEADER SIGNAL OPERATIONS
(410) 787-7652

CONTACTS FOR MONTGOMERY COUNTY

MR. ROBERT GONZALAS

### EQUIPMENT LIST "B"

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY CONTRACTOR ALL EQUIPMENT SHALL HAVE CATALOG CUTS SUBMITTED TO OOTS FOR APPROVAL PRIOR TO INSTALLATION.

ITEM NO.	QUANTITY	DESCRIPTION
1001	1 EA	MAINTENANCE OF TRAFFIC
2001	4 CY	CLASS 2 EXCAVATION
5003	200 LF	FURNISH AND INSTALL 12 IN. WHITE HEAT APPLIED PERMANENT THERMOPLASTIC PAVEMENT MARKING
6003	190 SF	FURNISH AND INSTALL 4 IN. CONCRETE SIDEWALK
8001	4 EA	FURNISH AND INSTALL 12 IN. PEDESTRIAN SIGNAL HEAD SECTION
5005	5 LF	REMOVE EXISTING PERMANENT PAVEMENT MARKING LINES
8010	1 E.A	FURNISH AND INSTALL CONDUIT BEND IN EXISTING BASE
8011	2 EA	FURNISH AND INSTALL PEDESTRIAN PUSHBUTTON AND SIGN
8026	10 LF	FURNISH AND INSTALL 2 IN. SCHEDULE 80 RIGID PVC CONDUIT - BORED
8056	570 LF	FURNISH AND INSTALL ELECTRICAL CABLE 2-CONDUCTOR
		NO. 14 AWG
8057	570 LF	FURNISH AND INSTALL ELECTRICAL CABLE 3-CONDUCTOR
		NO. 14 AWG
8070	20 LF	FURNISH AND INSTALL DEPRESSED CURB AND GUTTER

# EQUIPMENT LIST "C"

C. EXISTING EQUIPMENT TO BE REMOVED BY THE CONTRACTOR AND DELIVERED TO THE STATE HIGHWAY ADMINISTRATION, 7491 CONNELLEY DRIVE, HANOVER, MARYLAND 21076. THE CONTRACTOR SHALL NOTIFY THE SHA AT (410) 787-7652 AT LEAST THREE DAYS IN ADVANCE OF DELIVERY.

ITEM NO.

QUANTITY

DESCRIPTION

NONE

ALL SIGNAL EQUIPMENT TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR

SHA#: MO32545E/PER TOD#: AT288-41

MARYLAND DOT - STATE HIGHWAY ADMINISTRATION
Office of Traffic & Safety
TRAFFIC ENGINEERING DESIGN DIVISION

TRAFFIC ENGINEERING DESIGN

GENERAL INFORMATION
MD 650 (NEW HAMPSHIRE AVE) AND ELTON ROAD/I-495 OFF RAMP

HILLENDALE, MARYLAND

DRAWN BY: M.HOWELL F.A.P. NO. TS NO. 1353 C SHEET NO. SCALE: NONE MONTGOMERY T.I.M.S. NO. T.I.M.S. NO.

LOG MILE: 1506500.97

F834

A.B.C.D.EC

A.B.C.D.EC

WIRING KEY

A-B 2 CONDUCTOR ELECTRICAL CABLE
(MD. 14 A.W.G.)

C-D 3 CONDUCTOR ELECTRICAL CABLE
(MD. 14 A.W.G.)

EC EXISTING CABLE

TRAFFIC CONCEPTS, INC.

325 Gambrills Road

Suite E

Gambrills, MD 21054

(410) 923-7101 CHECKED
SCALE:
FAX (410) 923-6473 EMAIL TRACONCEPT@AOL.COM DATE: