PROJECT DESCRIPTION

I. GENERAL

This portion of the project involves the modification of the existing traffic interconnect from the intersection of MD 202 and 57th Ave to MD 202 and US 50 in Prince George's County Maryland. MD 202 runs in an East-West direction.

III. SPECIAL NOTES

- 1. It is the responsibility of the contractor to confirm geometrics prior to placing signal equipment.
- 2. The signal shop will be notified to perform internal wiring of the cabinet at the following intersections: MD 202 @ 57th Ave; MD 202 @ B.W. Parkway N.B; MD 202 @ B.W. Parkway S.B.; MD 202 @ Cheverly; MD 202 @ 62nd Ave.; MD 202 @ Kilmer St.; MD 202 @ US 50. All cable shall be identified and brought into the controller by the contractor. The contractor shall notify Mr. Edward Rodenhizer, SHA Signal Shop at (410) 787-7650 seventy-two (72) hours in advance of this work.
- 3. The Maryland State Highway Administration District #3 will be given at least seven (7) days notice to perform striping through the intersection area. Contact Mr. Majid Shakib at (301) 513 - 7358 to initiate this operation.
- 4. The project shall follow the Standard MOT Plates.

THE FOLLOWING CONTACT PERSONS FOR DISTRICT # 3 ARE AS FOLLOWS:

Mr.Lee Starkloff District Engineer Phone: (30I) 5I3-73I8

Mr. Raleigh Medley Asst. District Engineer - Maintenance Phone: (301) 513-7304

Mr. Augie Rebish Engineer-Utility Phone: (30I) 5I3-7350

Mr. Richard L. Daff Chief Traffic Operations Division Phone: (410) 787-7630

Mr. Majid Shakib Assistant District Engineer-Traffic Phone: (301) 513-7358

The Power Company Representative is: POTOMAC ELECTRIC POWER COMPANY

8300 OLD MARLBORO PIKE UPPER MARLBORO MARYLAND, 20772 (301) 961-5325

EQUIPMENT LIST

B. EQUIPMENT TO BE FURNISHED AND INSTALLED BY THE CONTRACTOR:

CATAGORY CODE NO.	SPEC. NO.	_QUANTITY_	DESCRIPTION
811001	811	9 EA.	FURNISH AND INSTALL ELECTRICAL HANDHOLE.
822001	810	3600 L.F.	FURNISH AND INSTALL 12 PAIR COMMUNICATION CABLE -SELF SUPPORTING (OVERHEAD).
822002	810	1500 L.F.	FURNISH AND INSTALL 12 PAIR COMMUNICATION CABLE -JELLYFILLED (UNDERGROUND)
870163	805	1800 L.F.	FURNISH AND INSTALL 3 IN. DIA. PVC ELECTRICAL CONDUIT SCHEDULE 80 - TRENCHED
870164	805	200 L.F.	FURNISH AND INSTALL 3 IN. DIA. PVC ELECTRICAL CONDUIT SCHEDULE 80 - BORED.



IC 7 OF 7

76 OF 92

REVISIONS MARYLAND DOT - STATE HIGHWAY ADMINISTRATION Office of Traffic & Safety TRAFFIC ENGINEERING DESIGN DIVISION MD 202 INTERCONNECT 57th STREET - US 50 GENERAL INFORMATION DRAWN BY: C. MUNZ CHECKED BY: C. MUNZ & 9/62 310 X7 S.H.A. NO. <u>PG4215184</u> SHEET NO.

COUNTY: PRINCE GEORGE'S

LOG MILE:

N.T.S.

AUG. 2002

SCALE:

DATE: 08/30/02

T.I.M.S. NO. E 691

FILE: m:*land_3*sp_202_int_gen.dgn