



**SPECIAL NOTE:**  
DISCONNECT EXISTING ELECTRICAL CABLE FROM EXISTING SIGNAL HEADS TO BE REMOVED AND RE-CONNECT TO PROPOSED SIGNAL HEADS. ANY SIGNAL OUTAGE SHALL BE SCHEDULED DURING NON-PEAK HOURS AS DIRECTED BY THE ENGINEER.

- GENERAL NOTES:**
- VIDEO CAMERA LOCATION / ALIGNING SHALL BE COORDINATED WITH THE SHA ENGINEER.
  - FOR FINAL PAVEMENT MARKINGS REFER TO THE PAVEMENT MARKING PLANS, OTHER THAN THOSE DETAILED ON THE PLAN. ALL PAVEMENT MARKINGS SHALL BE INSTALLED IN ACCORDANCE WITH MSHA STANDARDS.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR TERMINATING ALL SIGNAL CABLE TO THE APPROPRIATE TERMINALS AND PROPERLY LABEL EACH CABLE.



- CONSTRUCTION DETAILS**
- INSTALL 3 IN. PVC SCHEDULE 80 ELECTRICAL CONDUIT - TRENCHED
  - INSTALL 3 IN. PVC SCHEDULE 80 ELECTRICAL CONDUIT - BORED
  - INSTALL HANDHOLE.
  - INSTALL 24 IN. HEAT APPLIED, WHITE PERMANENT PREFORMED THERMOPLASTIC PAVEMENT MARKING FOR STOP LINE.
  - INSTALL 12 IN. HEAT APPLIED, WHITE PERMANENT PREFORMED THERMOPLASTIC PAVEMENT MARKING FOR CROSSWALKS.
  - USE EXISTING HANDHOLE.
  - USE EXISTING CONDUIT.
  - RELOCATE EXISTING SIGN AND SUPPORT(S).
  - INSTALL CONCRETE FOUNDATION WITH 10 FT. STEEL PEDESTAL POLE WITH BREAKAWAY BASE, 16 IN. PEDESTRIAN COUNTDOWN SIGNAL HEAD, AUDIBLE/TACTILE PEDESTRIAN PUSHBUTTON INSTALLED WITH VIBRATING ARROW POINTING RIGHT AND R10-4(1) SIGN TO READ "PUSHBUTTON TO CROSS PALMER ROAD". (NOTE: ONE 3 IN. PVC SCHEDULE 80 CONDUIT BEND).
  - USE EXISTING CABINET AND CONTROLLER. INSTALL AUDIBLE/TACTILE PEDESTRIAN PUSHBUTTON BASE UNIT.
  - USE EXISTING STEEL STRAIN POLE. REMOVE EXISTING PUSHBUTTON AND SIGN. INSTALL 16 IN. COUNTDOWN PEDESTRIAN SIGNAL HEAD AS NOTED.
  - USE EXISTING STEEL STRAIN POLE. INSTALL 16 IN. COUNTDOWN PEDESTRIAN SIGNAL HEAD AS NOTED AND ONE 3 IN. PVC SCHEDULE 80 CONDUIT BEND IN EXISTING FOUNDATION.
  - INSTALL CONCRETE FOUNDATION WITH 10 FT. STEEL PEDESTAL POLE WITH BREAKAWAY BASE, AUDIBLE/TACTILE PEDESTRIAN PUSHBUTTON INSTALLED WITH VIBRATING ARROW POINTING LEFT AND R10-(1) SIGN TO READ "PUSHBUTTON TO CROSS INDIAN HEAD HIGHWAY". CUT POLE ABOVE R10-4(1). (NOTE: ONE 3 IN. PVC SCHEDULE 80 CONDUIT BEND).
  - REMOVE EXISTING PAVEMENT MARKING (CROSSWALK).
  - ADJUST EXISTING HANDHOLE TO FINAL GRADE.
  - USE EXISTING SPAN WIRE. INSTALL SIGNAL HEADS AND SIGN. RELOCATE EXISTING SIGNAL HEAD AND SIGN AND REMOVE EXISTING SIGNAL HEADS AND SIGN AS NOTED. RELOCATING EXISTING SIGN WILL NOT BE MEASURED BUT WILL BE INCIDENTAL TO OTHER PERTINENT ITEMS IN THE CONTRACT.
  - USE EXISTING SPAN WIRE.
  - USE EXISTING SPAN WIRE. INSTALL SIGNAL HEADS AND SIGN AND REMOVE EXISTING SIGNAL HEADS AND SIGN AS NOTED.
  - USE EXISTING STRAIN POLE.
  - INSTALL CONCRETE FOUNDATION WITH 10 FT. STEEL PEDESTAL POLE WITH BREAKAWAY BASE, AUDIBLE/TACTILE PEDESTRIAN PUSHBUTTON INSTALLED WITH VIBRATING ARROW POINTING RIGHT AND R10-(1) SIGN TO READ "PUSHBUTTON TO CROSS INDIAN HEAD HIGHWAY". CUT POLE ABOVE R10-4(1). (NOTE: ONE 3 IN. PVC SCHEDULE 80 CONDUIT BEND).
  - INSTALL CONCRETE FOUNDATION WITH 10 FT. STEEL PEDESTAL POLE WITH BREAKAWAY BASE, AUDIBLE/TACTILE PEDESTRIAN PUSHBUTTON INSTALLED WITH VIBRATING ARROW POINTING LEFT AND R10-4(1) SIGN TO READ "PUSHBUTTON TO CROSS PALMER ROAD". CUT POLE ABOVE R10-4(1) SIGN. (NOTE: ONE 3 IN. PVC SCHEDULE 80 CONDUIT BEND).

- GENERAL NOTES CONTINUED**
- THE CONTRACTOR SHALL VERIFY ALL UNDERGROUND UTILITIES PRIOR TO INSTALLING PROPOSED SIGNAL EQUIPMENT. IF ANY UTILITY CONFLICTS SHOULD ARISE THE CONTRACTOR SHALL CONTACT THE PROJECT ENGINEER.
  - ALL TRAFFIC SIGNAL FOUNDATIONS SHALL BE INSTALLED AT THE FINAL SIDEWALK OR CURB GRADE FOR CLOSED SECTIONS, HIGHEST ROADWAY PROFILE GRADE FOR OPEN SECTIONS, TO MEET CLEARANCES AS SPECIFIED IN MD 816.03, MD 818.01, MD 818.02, MD 818.04. THE CONTRACTOR SHALL VERIFY ULTIMATE GRADES PRIOR TO THE INSTALLATION OF ALL SIGNAL EQUIPMENT.
  - ALL EXISTING TRAFFIC SIGNAL EQUIPMENT REMOVED SHALL BECOME THE PROPERTY OF THE SIGNAL CONTRACTOR UPON COMPLETION OF THE NEW SIGNAL.



**WR&A**  
Whitman, Reardon  
and Associates, LLP  
801 South Caroline Street  
Baltimore, Maryland 21231  
(410) 235-3450

**APPROVALS**

TEAM LEADER	
ASST. DIV. CHIEF	
DIVISION CHIEF	
OFFICE DIRECTOR	

**REVISIONS**

1	INSTALLED PED SIGNALS ACROSS PALMER ROAD	2/10/06
2	SPLIT SIDE ROAD PHASING	10/2/05
3	REPLACE FAILED SIDE ROAD LOOP DETECTORS	7/91

**SIGNALIZATION PLAN**

SCALE 1" = 20' DATE 1/19/06 CONTRACT NO. P-920-501-371

DESIGNED BY DCD COUNTY PRINCE GEORGES  
DRAWN BY DCD LOGMILE 16.02 | 010.61  
CHECKED BY S.R. T.I.M.S. NO. H769  
F.A.P. NO. TOD NO. TS-918 F

DRAWING NO. TSP-1- 1 OF 5 SHEET NO. OF