TOD NO: XY224-29
SHA NO: CA227B51
MD 2-4 @ Old Field Lane/Sherry Lane

MD 2–4 IS ASSUMED TO RUN IN A NORTH/SOUTH DIRECTION

OLD FIELD LANE

PEPCO# P300037

MD 2–4 NB (SOLOMON'S ISLAND ROAD)

MD 2–4 SB (SOLOMON'S ISLAND ROAD)

SHERRY LANE

GEOMETRIC CONSTRUCTION DETAILS:

A. INSTALL PARALLEL SIDEWALK RAMP (STANDARD NO. MD 655.12).
B. INSTALL COMBINATION SIDEWALK RAMP (STANDARD NO. MD 655.13).
C. INSTALL STANDARD TYPE A COMBINATION CURB AND GUTTER. (STANDARD NO. MD 620.02)
D. INSTALL STANDARD TYPE A CURB (STANDARD NO. MD 620.02).
E. BEGIN 12:1 RAMP.
F. 48:1 LEVEL LANDING AREA.
G. TIE IN RAMP WITH EXISTING SIDEWALK AT JOINT.
H. TIE NEW CURB TO EXISTING CURB AT JOINT.
J. BACKFILL WITH SEED AND MULCH.

GEOMETRIC LEGEND

EXISTING SIDEWALK/CURB JOINT (APPROXIMATE)

NEW SIDEWALK AND ADA HANDICAP RAMP

SEED AND MULCH

GEOMETRIC LEGEND

EXISTING
PROPOSED

UTILITY LEGEND

SD	STORM DRAIN
G	GAS MAIN
W	WATER MAIN
S	SEWER MAIN
E	ELECTRIC CABLES
A	AERIAL CABLES
T	TELEPHONE CABLES
F	FIBER-OPTIC CABLES

BRUDIS & ASSOCIATES, INC.
Consulting Engineers
9240 Rumsey Road; Suite C
Columbia, Maryland 21045
Phone 410-884-3607
www.brudis.com

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF TRAFFIC & SAFETY
TRAFFIC ENGINEERING DESIGN DIVISION
TRAFFIC SIGNALIZATION PLAN
MD 2-4 AND OLD FIELD LANE
(PRINCE FREDERICK, MD)

DETAIL PLAN SHEET

SCALE 1" = 10' ADVERTISED DATE 04/2013 CONTRACT NO. XY2245185

DESIGNED BY	JC	COUNTY	CALVERT
DRAWN BY	JC	LOGMILE	04000218.18
CHECKED BY	RM	TIMS NO.	L686
F.A.P. NO.		TOD NO.	

TS NO. 3921 D | DRAWING SG-2 OF 3 | SHEET NO. 2 OF 4

PLOTTED: Tuesday, March 19, 2013 AT 03:59 PM
FILE: P:\09-002 TEDD\Task 112 MD2-4 @ Old Field Ln\Drawings\CADD\Working\pSG-P002_MD2-4@OldField.dgn

BY: jay –