



BY: jmoorty

PROJECT DESCRIPTION	EQUIPMENT LIST "A"	EQUIPMENT LIST "B"																								
<p><u>GENERAL</u></p> <p>THIS PROJECT INVOLVES THE INSTALLATION OF AN ADVANCED LANE USE CONTROL SIGN ON THE NORTHBOUND MD 910 (WESTERN MARYLAND PARKWAY) APPROACH TO US 40, AS WELL AS A SPAN MOUNTED LANE USE CONTROL SIGN AT THE SIGNALIZED INTERSECTION. THE INTERSECTION IS LOCATED IN WASHINGTON COUNTY, MARYLAND. US 40 IS ASSUMED TO RUN IN AN EAST-WEST DIRECTION.</p> <p><u>INTERSECTION OPERATION</u></p> <p>THE US 40 AND MD 910 (WESTERN MARYLAND PARKWAY) INTERSECTION OPERATION WILL REMAIN THE SAME.</p> <p><u>CONTROLLER REQUIREMENTS</u></p> <p>THE EXISTING BASE MOUNTED CABINET AND CONTROLLER WILL REMAIN.</p>	<p>A. EQUIPMENT TO BE SUPPLIED BY THE SHA</p> <table><thead><tr><th>ITEM NO.</th><th>QUANTITY</th><th>DESCRIPTION</th></tr></thead><tbody><tr><td>9570</td><td>28 S.F.</td><td>SHEET ALUMINUM GROUND MOUNTED SIGNS TO CONSIST OF : - 1 EACH GM-1 (84 IN. x 48 IN.)</td></tr><tr><td>9571</td><td>18 S.F.</td><td>SHEET ALUMINUM OVERHEAD MOUNTED SIGNS TO CONSIST OF : - 1 EACH R3-5(2) MOD (60 IN. x 42 IN.) - SPAN WIRE MOUNT</td></tr></tbody></table> <p><u>EQUIPMENT LIST "C"</u></p> <p>C. EQUIPMENT TO BE REMOVED AND RETURNED TO SHA NO EQUIPMENT TO BE REMOVED AND RETURNED TO SHA</p> <p><u>MAINTENANCE OF TRAFFIC</u></p> <p>THE FOLLOWING TRAFFIC CONTROL STANDARDS SHALL BE REFERENCED FOR THE PROJECT. ADDITIONAL TRAFFIC CONTROL STANDARDS MAY BE USED AS DIRECTED BY THE ENGINEER.</p> <p>STANDARD NO. MD-104.03-06 (RIGHT LANE CLOSURE) STANDARD NO. MD-104.06-10 (MOBILE SERVICE WORK/INTERSECTION)</p>	ITEM NO.	QUANTITY	DESCRIPTION	9570	28 S.F.	SHEET ALUMINUM GROUND MOUNTED SIGNS TO CONSIST OF : - 1 EACH GM-1 (84 IN. x 48 IN.)	9571	18 S.F.	SHEET ALUMINUM OVERHEAD MOUNTED SIGNS TO CONSIST OF : - 1 EACH R3-5(2) MOD (60 IN. x 42 IN.) - SPAN WIRE MOUNT	<p>B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR</p> <table><thead><tr><th>ITEM NO.</th><th>QUANTITY</th><th>DESCRIPTION</th></tr></thead><tbody><tr><td>1001</td><td>1 EACH</td><td>MAINTENANCE OF TRAFFIC (PER ASSIGNMENT)</td></tr><tr><td>8023</td><td>1 EACH</td><td>REMOVE & DISPOSE OF EQUIPMENT</td></tr><tr><td>8039</td><td>52 LF</td><td>WOOD SIGN SUPPORTS UP TO 4" X 6"</td></tr><tr><td>8040</td><td>46 SF</td><td>INSTALL OVERHEAD OR GROUND MOUNTED SIGN (INCLUDING ALL HARDWARE)</td></tr></tbody></table>	ITEM NO.	QUANTITY	DESCRIPTION	1001	1 EACH	MAINTENANCE OF TRAFFIC (PER ASSIGNMENT)	8023	1 EACH	REMOVE & DISPOSE OF EQUIPMENT	8039	52 LF	WOOD SIGN SUPPORTS UP TO 4" X 6"	8040	46 SF	INSTALL OVERHEAD OR GROUND MOUNTED SIGN (INCLUDING ALL HARDWARE)
ITEM NO.	QUANTITY	DESCRIPTION																								
9570	28 S.F.	SHEET ALUMINUM GROUND MOUNTED SIGNS TO CONSIST OF : - 1 EACH GM-1 (84 IN. x 48 IN.)																								
9571	18 S.F.	SHEET ALUMINUM OVERHEAD MOUNTED SIGNS TO CONSIST OF : - 1 EACH R3-5(2) MOD (60 IN. x 42 IN.) - SPAN WIRE MOUNT																								
ITEM NO.	QUANTITY	DESCRIPTION																								
1001	1 EACH	MAINTENANCE OF TRAFFIC (PER ASSIGNMENT)																								
8023	1 EACH	REMOVE & DISPOSE OF EQUIPMENT																								
8039	52 LF	WOOD SIGN SUPPORTS UP TO 4" X 6"																								
8040	46 SF	INSTALL OVERHEAD OR GROUND MOUNTED SIGN (INCLUDING ALL HARDWARE)																								
<p><u>PROJECT CONTACTS</u></p> <p>THE CONTACT PERSONS FOR SHA ARE AS FOLLOWS:</p> <div><p>MR. GEORGE H. SMALL ASSISTANT DISTRICT ENGINEER - TRAFFIC PHONE: (301) 729-8444</p><p>MR. DWAYNE BITTNER ASSISTANT DISTRICT ENGINEER - MAINTENANCE PHONE: (301) 729-8457</p><p>MR. EDWARD RODENHIZER MANAGER, SIGNAL OPERATIONS PHONE: (410) 787-7652</p></div> <div><p>MR. DAVID LARRICK DISTRICT UTILITY ENGINEER PHONE: (301) 729-8420</p><p>MR. RICHARD L. DAFF, SR. CHIEF, TRAFFIC OPERATIONS DIVISION PHONE: (410) 787-7630</p><p>MR. SONNY BAILEY MANAGER, SIGN OPERATIONS PHONE: (410) 787-7678</p></div>																										

TOD NO: XX650-10
SHA NO: WA227B51
US 40 @ Western Maryland Parkway

WHITMAN, REQUARDT & ASSOCIATES, LLP
801 South Caroline Street, Baltimore, Maryland 21231

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF TRAFFIC & SAFETY
TRAFFIC ENGINEERING DESIGN DIVISION
US 40 AT WESTERN MARYLAND PARKWAY
(HAGERSTOWN, MD)

GENERAL INFORMATION SHEET

SCALE NONE DATE NOVEMBER 14, 2011 CONTRACT NO. XX65051B5

DESIGNED BY J. RASMUSSEN COUNTY WASHINGTON
DRAWN BY J. RASMUSSEN LOGMILE 34.640
CHECKED BY N. LEARY TMS NO. 1098
F.A.P. NO. _____ TOD NO. _____

TS NO. 3300A DRAWING **TSP-03** OF 3 SHEET NO. 3 OF 3

PLOTTED: November 22, 2011
FILE: N:\91669-182\CA00\p25G-N003_U840.dgn